



PROPOSED SECOND FLOOR PLAN

KEEP

- All existing glazed partitions & offices
- Existing radiators
- Fixed furniture - Reception desk & storage near rear fire exist
- Grid ceiling
- Floor boxes
- Existing ceiling lights

REMOVE & NEW

- Main door
- New toilet layout as shown
- New budget carpet (Dark Grey) through out. Add wood floor near reception/ main door.
- Remove all existing CCTV camers. Keep all cabling for future use.
- New partition as shown
- New Tea-Prep with new tile finish to back wall (dishwasher + Sink + Hot tap + Drawers + Bin + provision for under counter integrated fridge.)
- Wall decoration
- Replacement of damaged ceiling tile with new tile.
- New works at lift lobby (same as level 1 lift lobby)

- New full height partition
- New wood floor